



CERTIFIED SOLAR COLLECTOR

SUPPLIER:
Solar Panels Plus
 2133 Smith Ave
 Chesapeake, VA 23320 USA
 www.solarpanelsplus.com

BRAND: Solar Panels Plus
 MODEL: SPP-30A
 COLLECTOR TYPE: Tubular
 CERTIFICATION #: 2008050D
 Original Certification: February 18, 2010
 Expiration Date: July 30, 2020

The solar collector listed below has been evaluated by the Solar Rating & Certification Corporation™ (SRCC™) in accordance with SRCC OG-100, Operating Guidelines and Minimum Standards for Certifying Solar Collectors, and has been certified by the SRCC. This award of certification is subject to all terms and conditions of the Program Agreement and the documents incorporated therein by reference.

COLLECTOR THERMAL PERFORMANCE RATING							
Kilowatt-hours (thermal) Per Panel Per Day				Thousands of Btu Per Panel Per Day			
Climate -> Category (Ti-Ta)	High Radiation (6.3 kWh/m ² .day)	Medium Radiation (4.7 kWh/m ² .day)	Low Radiation (3.1 kWh/m ² .day)	Climate -> Category (Ti-Ta)	High Radiation (2000 Btu/ft ² .day)	Medium Radiation (1500 Btu/ft ² .day)	Low Radiation (1000 Btu/ft ² .day)
A (-5 °C)	13.9	10.5	7.0	A (-9 °F)	47.4	35.7	24.0
B (5 °C)	13.4	10.0	6.5	B (9 °F)	45.8	34.0	22.3
C (20 °C)	12.5	9.1	5.7	C (36 °F)	42.8	31.1	19.4
D (50 °C)	10.7	7.2	3.9	D (90 °F)	36.4	24.7	13.2
E (80 °C)	8.5	5.2	2.0	E (144 °F)	28.8	17.9	7.0

A- Pool Heating (Warm Climate) **B-** Pool Heating (Cool Climate) **C-** Water Heating (Warm Climate)
D- Space & Water Heating (Cool Climate) **E-** Commercial Hot Water & Cooling

COLLECTOR SPECIFICATIONS					
Gross Area:	4.810 m ²	51.78 ft ²	Dry Weight:	86 kg	190 lb
Net Aperture Area:	4.157 m ²	44.74 ft ²	Fluid Capacity:	1.6 liter	0.4 gal
Absorber Area:	0.000 m ²	0.00 ft ²	Test Pressure:	600 kPa	87 psi

TECHNICAL INFORMATION		Tested in accordance with:			
ISO Efficiency Equation [NOTE: Based on gross area and (P)=Ti-Ta]					
SI UNITS:	$\eta = 0.477 - 0.93740(P/G) - 0.00655(P^2/G)$	Y Intercept:	0.481	Slope:	-1.334 W/m ² .°C
IP UNITS:	$\eta = 0.477 - 0.16521(P/G) - 0.00064(P^2/G)$	Y Intercept:	0.481	Slope:	-0.235 Btu/hr.ft ² .°F

Transverse Incident Angle Modifier								Longitudinal Incident Angle Modifier at 50°:		
θ	10	20	30	40	50	60	70	Test Fluid:	Water	
K_{τα}	1.01	1.06	1.12	1.18	1.17	0.78	-1.53	Test Mass Flow Rate:	0.0202 kg/(s m ²)	14.88 lb/(hr ft ²)

REMARKS:

Jen Higgins

Technical Director





CERTIFIED SOLAR COLLECTOR

SUPPLIER:
Solar Panels Plus
 2133 Smith Ave
 Chesapeake, VA 23320 USA
 www.solarpanelsplus.com

BRAND: Solar Panels Plus
 MODEL: SPP-30A
 COLLECTOR TYPE: Tubular
 CERTIFICATION #: 2008050D
 Original Certification: February 18, 2010
 Expiration Date: July 30, 2020

The solar collector listed below has been evaluated by the Solar Rating & Certification Corporation™ (SRCC™) in accordance with SRCC OG-100, Operating Guidelines and Minimum Standards for Certifying Solar Collectors, and has been certified by the SRCC. This award of certification is subject to all terms and conditions of the Program Agreement and the documents incorporated therein by reference.

ADDITIONAL INFORMATION (click here to return to the rating page)			
Test Lab:	Bodycote	Test Report Date:	July 30, 2008
Test Report Number:	07-08-0528	Test conducted:	

SOLAR COLLECTOR CONSTRUCTION DETAILS					
Header Enclosure:					
Gross Length:	0.000 m	Gross Width:	0.000 m	Gross Depth:	
Tube Bank:					
Gross Length:		Gross Width:			

COLLECTOR MATERIALS					
Outer Cover:	Other	Enclosure back:	Steel	Back Insulation:	,
Inner Cover:	None	Enclosure side:	Steel	Side Insulation:	,
Absorber Description:		Flow Pattern:			
Riser Tube:	Copper	Fin:			
Absorber Coating:	Selective	Tube to fin connection			

Glazing	Outer Cover	Inner Cover
Material:	Other	None
Surface Characteristics:		
Thickness:	0.0 mm	N/A
Transmissivity:		
Gross Tube Length (uninstalled):	0.000 m	
Diameter:	0.000 m	
Tube Glazing to Header Enclosure Seal:		
Reflector Shape:		Reflector Material:

ABSORBER:





Header Material:		Header OD:		Header Wall:	
Riser Tube Material:	Copper	Riser Tube OD:		Riser Tube Wall Thickness:	
Fin Material:		Fin Thickness:	0.00 mm		
Flow Pattern:		Number of Flow Tubes / Heat Pipes:	0	Tube / Heat Pipe Spacing:	
Number of absorber tubes:	0	Flow Tube to Fin Bond:		Length of Flow Path:	0.00 m
Length of Flow Path:	0.00 m	Riser to Fin/Plate Bond:			

INSULATION:					
Location	Type	Thickness	Location	Type	Thickness
Back – Top Layer:			Sides – Inner Layer:		
Back – Bottom Layer:			Sides – Outer Layer:		
Enclosure Fastening Methods:			Header Enclosure:		

Power Output per Collector(W) [Ti-Ta, G = 1000 W/m ²]				
0	10	30	50	70

PRESSURE DROP				
Flow	ΔP		Flow	ΔP
ml/s	Pa		gpm	in H ₂ O
20			0.32	
50			0.79	
80			1.27	

